

Just there  
spec  
Reveal  
CHS  
Rail of the  
National  
Historic  
Note 1. cannot  
Reveal a  
Historic

& SBC? for  
recommendation

get with  
Sean Brander & do a site visit  
comment on  
RT entry

has input



Coastal Georgia / East Coast Greenway &  
Heritage Trail  
Cost Estimate  
High Priority Project '09

ITEM	DESCRIPTION	Jo's items QUANTITY	CHS items QUANTITY	TOTAL QUANTITY	UNIT	UNIT PRICE	AMOUNT
1	Traffic Control	9		9	Days	\$60.00	\$540.00
2	Temporary Grassing	13		13	AC	\$240.00	\$3,120.00
3	Silt Fence. Type B	70		70	LF	\$2.50	\$175.00
4	Maintenance of Silt Fence	70		70	LF	\$0.50	\$35.00
5	Grading	94		94	SY	\$2.60	\$244.40
6	Borrow			0	BCY	\$12.00	\$0.00
7	Special subgrade compaction test 1/mile			0	EA	\$200.00	\$0.00
8	Concrete Pavement (4 inch)	63		63	SY	\$21.75	\$1,370.25
9	Signs, Type I, reflective shtg	75		75	SF	\$14.00	\$1,050.00
10	Galv. Steel U- Post, (Type 2) 12'	144		144	LF	\$9.25	\$1,332.00
11	Trail Logo Sign (special design)	21		21	EA	\$1,500.00	\$31,500.00
12	Kiosk (special design)	7		7	EA	\$7,000.00	\$49,000.00
13	24" x 36" low profile NPS type al. sign & base, complete	5		5	EA	\$1,000.00	\$5,000.00
14	6" Pavement Makring, White Thermoplastic	41,760		41760	LF	\$1.50	\$62,640.00
15	Bike Symbol, pavement marking	34		34	EA	\$55.00	\$1,870.00
16	10' Bicycle Rack and conc. Base, complete	6		6	EA	\$650.00	\$3,900.00
17	Trash receptacle w/ liner & base, complete	7		7	EA	\$450.00	\$3,150.00
18	Picnic table w/ conc. base, complete	8		8	EA	\$1,250.00	\$10,000.00
19	Hcap. Picnic table w/ conc. base, complete	2		2	EA	\$1,500.00	\$3,000.00
20	40" metal fencing w/ posts 6' o.c., complete	325		325	LF	\$40.00	\$13,000.00
21	20' x 30' Picnic Shelter, (no restrooms) complete	600		600	SF Flr	\$50.00	\$30,000.00
22	4' bench w/ base, complete	16		16	EA	\$500.00	\$8,000.00
23	2" calip Live Oak, installed	22		22	EA	\$425.00	\$9,350.00
24	7' Ht. Multi-stem Crape Myrtle, installed	10		10	EA	\$380.00	\$3,800.00
25	12' Ht. Palmetto, installed	12		12	EA	\$400.00	\$4,800.00
26	2 gal shrub, installed	440		440	EA	\$15.00	\$6,600.00
27	Wooden Ped/Bike Bridge (10' x 50') & supports, complete	500		500	SF	\$85.00	\$42,500.00
28	Permanent Grassing	13		13	AC	\$300.00	\$3,900.00
29	Ag. Lime @ 1 tn/ac	13		13	TN	\$50.00	\$650.00
30	Liquid Lime @ 2 gal/ac	26		26	GAL	\$17.50	\$455.00
31	Fertilizer, mixed grade @ 0.6 tn/ac	7.8		7.8	TN	\$300.00	\$2,340.00
32	Fertilizer, nitrogen @ 36 lbs/ac	468		468	LBS	\$1.20	\$561.60
33	Biodegradable paper mulch	62,920		62920	SY	\$0.40	\$25,168.00

\$329,051.25